

# OBION COUNTY BOARD OF EDUCATION

## HVAC UPGRADES

### SOUTH FULTON HIGH SCHOOL

#### ADDENDUM #1

In the unit schedule there is an error on the listing for unit **RTU 15**.

This unit should be listed as **PKG #15**. This unit is to be bid as the **requested alternate**.

The existing unit model number is **48TFE014-A-611**, serial number is **0204G40520**.

The unit is pad mounted with side supply and return.

Power is 480 volts, 3 phase, with natural gas heat.

Unit is to include hail guards, and manual 0-25% outside air damper.

410 A refrigerant

5 year complete parts and compressor warranty.

**All control work is to be provided by the Obion County Board of Education (without exception).**

**Base bid is not to include any primary electrical work.**

**If bidder wishes to include primary electrical work he may do so using the voluntary alternate lines on the bid form. The following requirements must be met:**

1. All electrical work must be performed by a licensed contractor.
2. All work is to meet current codes.
3. All units will require new disconnects. Each disconnect mounted on units are to be rated outdoor, rain-tight, with proper voltage and amps to match new units.
4. New breakers will be required for RTU #12 and #13. These are to be Westinghouse type EHD 480 volt, 3 phase, rated 30 amp. Westinghouse cat number EHD 3030. Installed in the boiler room distribution panel.
5. All wire sizes are to match that in existence.

Any questions or clarifications may be addressed to:

Phil Graham  
Maintenance Supervisor  
Office phone 731-536-4226  
Cell phone 731-446-2139  
grahamp@k12tn.net